

## ABSTRACT OF THE DISCLOSURE

A method of installing preformed unibody diverter units around building foundations to direct water away from the building foundation including performing the diverter units to have a vertical section and an angled section, 5 preparing the soil surrounding the building foundation, and coupling the vertical section to the building housing.